



**Jim Bushnell**

11 Grange Road, Bearley,

07988207425

07988207425

Nellybushnell@googlemail.com

www.priceajob.co.uk

## Quote

jim bushnell

**Ref:**

JOB-161

Cricket pavillion

Stratford-upon-Avon

England

### Site Work



#### Fences and Barriers

**£1,548.44**

##### Fences 1.

Heras Fence, 95.3 m

- ✓ Hire Heras Fence for 6 Weeks
- ✓ Hire 90m of Heras Fence Panel 3.5m x 2m
- ✓ 1 x Pedestrian gate
- ✓ 1 x Vehicle gate
- ✓ We have allowed for delivery and collection cost

##### Labour

Description	Qty	Unit	Rate (£)	Value (£)
Install Temporary Fence	95.3	m	£2.41	£229.64

##### Plant & Tool

Description	Qty	Term	Unit	Rate (£)	Value (£)
Delivery and Collection Cost	1	-	each	£45.00	£45.00
Heras Fence Panel Standard 3.5m x 2m	26	6.0	week	£6.80	£1,060.80
Pedestrian Gate For 1.1m Heras Fence	1	6.0	week	£4.90	£29.40
Vehicle Gate 4.2m - Heras Fence	1	6.0	week	£30.60	£183.60



#### Scaffolding

**£7,488.00**

##### Scaffolding 1.

Static Scaffolding - 240 m<sup>2</sup>

- ✓ Provide Scaffolding for 10 Weeks, Height - 4m, Width - 60m

##### Plant & Tool

Description	Qty	Term	Unit	Rate (£)	Value (£)
Provide Scaffolding for 10 weeks, Height - 4m, Width - 60m	1	1.0	each	£6,912.00	£6,912.00

##### Other costs

Description	Qty	Unit	Rate (£)	Value (£)
Extra charge	1.0	each	£576.00	£576.00

## Drain Runs

**£2,702.10**

### Drainage run construction:

- ✓ Excavate trench 440mm deep by hand
- ✓ Levelling and compacting bottoms of excavations with vibrating plate
- ✓ Disposal of surplus excavated material off site
- ✓ We have allowed for 1 x 8 Yard Skip 3.6m(L) x 1.7(W) x 1.2(H)
- ✓ We have allowed for 1 x 1 Tonne Skip Loader
- ✓ Bedding and surround in pea gravel
- ✓ 15 - Underground Pipe 3m - Single Socket 110mm
- ✓ Double Socket Junctions 45° 110mm - 6 each
- ✓ Long Radius Bend 110mm - 4 each
- ✓ Access Bend 110mm - 4 each
- ✓ Socket Plug 110mm - 4 each
- ✓ Universal Gully Trap 110mm - 4 each
- ✓ Back Inlet Bottle Gully-Round - 3 each
- ✓ P Trap 110mm - 3 each
- ✓ Flexible Adaptors 121-136 mm x 100-115 mm /110mm - 2 each
- ✓ Backfilling to trench with Soil.

### Material

Description	Qty	Unit	Rate (£)	Value (£)
Underground Pipe 3m - Single Socket 110mm	15.0	each	£15.05	£225.75
Long Radius Bend 110mm	4.0	each	£23.33	£93.32
Access Bend 110mm	4.0	each	£17.50	£70.00
Socket Plug 110mm	4.0	each	£4.15	£16.60
Back Inlet Bottle Gully-Round	3.0	each	£29.57	£88.71
Universal Gully Trap 110mm	4.0	each	£11.53	£46.12
P Trap 110mm	3.0	each	£17.82	£53.46
Flexible Adaptors 121-136 mm x 100-115 mm /110mm	2.0	each	£11.23	£22.46
Double Socket Junctions 45° 110mm	6.0	each	£11.15	£66.90
10mm Gravel/Shingle Bulk Bag	9.3	each	£62.50	£579.38

### Labour

Description	Qty	Unit	Rate (£)	Value (£)
Install drainage pipes and fittings	13.1	hour	£22.00	£288.20
Fill to excavations by hand	4.4	m3	£20.00	£87.60
Levelling and compacting bottoms of excavations	15.4	m2	£2.00	£30.80
Excavate trenches by Hand	6.8	m3	£81.48	£552.44
Load soil to Skip By Machine	3.7	hour	£22.00	£80.74
Fill to make up levels by hand	2.0	m3	£42.31	£84.62

### Plant & Tool

Description	Qty	Term	Unit	Rate (£)	Value (£)
8 Yard Skip 3.6m(L) x 1.7(W) x 1.2(H)	1	-	each	£255.00	£255.00
1 Tonne Skip Loader	1	1.0	day	£60.00	£60.00

## Substructure



### Foundation

**£8,203.01**

**Trench Foundation. Length 55m:**

- ✓ Excavate trenches by machine, Width - 600mm, Depth - 1000mm
- ✓ Levelling and compacting bottoms of excavations with vibrating plate
- ✓ We have allowed for 1 x 3 Tonne Excavator
- ✓ Disposal of surplus excavated material off site
- ✓ We have allowed for 6.4 x Grab Lorry 10t
- ✓ We have allowed for 1 x 1 Tonne Skip Loader
- ✓ Ready mixed concrete - C25 Mix

**Material**

Description	Qty	Unit	Rate (£)	Value (£)
Concrete Mix C25	24.8	m3	£117.00	£2,895.75
Regular Diesel	107.8	l	£1.90	£204.82

**Labour**

Description	Qty	Unit	Rate (£)	Value (£)
Load soil to Skip By Machine	25.4	hour	£22.00	£557.92
Casting concrete to trench	24.8	m3	£41.80	£1,034.55
Levelling and compacting bottoms of excavations	33.0	m2	£2.00	£66.00
Excavate trenches by Machine	33.0	m3	£35.48	£1,170.97

**Plant & Tool**

Description	Qty	Term	Unit	Rate (£)	Value (£)
Grab Lorry 10t	6.4	1.0	each	£295.00	£1,888.00
1 Tonne Skip Loader	1	1.0	day	£60.00	£60.00
3 Tonne Excavator	1	3.0	day	£93.33	£280.00
Delivery and Collection Cost	1	-	each	£45.00	£45.00

**Cavity Walls Below DPC****£4,164.74****Cavity Walls Below DPC.**

- ✓ Constructed in cement sand mortar 1:3
- ✓ Outer skin: concrete blocks below ground level and bricks above ground level
- ✓ Supply and install Class B Red Perforated Engineering Brick 65mm
- ✓ Cavity formed with stainless steel wall ties, cavity 150mm wide
- ✓ Site mixed concrete
- ✓ Concrete blocks inner skin
- ✓ Damp proof course built into walls
- ✓ 2 x General Labourers for 1 x Week

**Material**

Description	Qty	Unit	Rate (£)	Value (£)
Ballast Bulk Bag	3.8	each	£62.50	£240.00
Blue Circle Mastercrete 25kg	29.2	each	£6.33	£184.84
Solid Low Density Concrete Blocks 3.6N 100mm	245.0	each	£3.57	£874.72
Sika Maxmix Concentrated Plasticiser 1L	0.0	each	£11.11	£0.44
Building Sand Bulk Bag	0.9	each	£62.50	£55.63
Blue Circle Cement 25kg	8.7	each	£5.75	£49.91
Damp Proof Course 100mm x 30m	3.7	each	£3.74	£13.73
Class B Red Perforated Engineering Brick 65mm	733.8	each	£1.20	£880.61

**Labour**

Description	Qty	Unit	Rate (£)	Value (£)
Mix Concrete on Site	1.9	m3	£22.50	£41.85

Filling cavity	1.9	m3	£54.05	£100.54
Laying concrete blocks	245.0	each	£1.68	£411.63
Lay damp proof course	110.0	m	£2.40	£264.00
Laying bricks (half a brick thick)	12.4	m2	£26.40	£326.83
General Labourer	80.0	hour	£9.00	£720.00



## Concrete Floors

**£19,205.50**

### Concrete Floor. Concrete ground floor slab, floor area 164.7m<sup>2</sup>:

- ✗ Disposal of surplus excavated materials not included
- ✓ 150mm backfilling to make up levels with hardcore obtained off site, compacting fill with vibrating plate
- ✓ 50mm sand or quarry dust blinding spread and levelled over hardcore, compacting blinding with vibrating plate
- ✓ 1200 gauge damp proof membrane
- ✓ Celotex or similar flooring insulation board, 100mm thick
- ✓ Celotex or similar flooring insulation board to perimeter of floor screed, 25mm thick x 175mm high
- ✓ 500 gauge separating layer/vapour barrier
- ✓ Ready mixed concrete - C25 Mix
- ✓ Mesh reinforcement to slab
- ✓ Cement and sand (1:3) floor screed, 75mm thick

### Material

Description	Qty	Unit	Rate (£)	Value (£)
25mm Celotex Insulation TB3025 Board 2400mm x 1200mm	3.1	each	£13.33	£41.59
Building Sand Bulk Bag	16.0	each	£62.50	£999.38
A393 Reinforcing Mesh 4.8m x 2.4m (6.2kg/m <sup>2</sup> )	14.3	each	£112.95	£1,615.19
Plastic Reinforced Mesh Spacers 40-50mm	1029.0	each	£0.44	£452.76
Visqueen Vapour Check 500 GA Green 4 x 50m	0.9	roll	£113.00	£98.31
Damp Proof Membrane 1200ga 4m x 3m (12m <sup>2</sup> )	15.0	each	£11.66	£175.02
MOT Type 1 Sub-base Bulk Bag	55.8	bag	£62.50	£3,487.50
Sharp Sand Bulk Bag	24.7	each	£62.50	£1,544.38
Blue Circle Mastercrete 25kg	240.6	each	£6.33	£1,523.19
Concrete and screed Fibres 900g (usage 1m <sup>3</sup> screed)	13.0	each	£16.67	£216.71
Concrete Mix C25	16.5	m3	£117.00	£1,926.99
100mm Celotex Insulation GA4100 Board 2400mm x 1200mm	57.2	each	£31.67	£1,811.21

### Labour

Description	Qty	Unit	Rate (£)	Value (£)
Laying insulation to floor	173.7	m2	£4.00	£694.72
Fill to make up levels by hand	33.0	m3	£42.31	£1,394.04
Spreading and Levelling Fill	329.4	m2	£0.79	£260.89
Compacting Fill	329.4	m2	£1.00	£329.40
Cutting and placing reinforcing mesh	164.7	m2	£2.22	£366.00
Laying vapour control	173.7	m2	£1.11	£192.98
Laying Damp Proof Membrane	180.1	m2	£1.00	£180.10
Laying floor screed 65-100mm	164.7	m2	£6.67	£1,098.00
Casting concrete to slabs	16.5	m3	£48.40	£797.15

## Structure



## External Walls

**£34,789.57**

### Cavity Wall. Area - 180 m<sup>2</sup>

- ✓ Outer Skin - Brick wall 102.5 mm thick in cement sand mortar (1:3)
- ✓ Supply and install London Brick Company Commons
- ✓ Cavity formed with stainless steel wall ties
- ✓ Inner Skin - Block wall 100 mm thick in cement sand mortar (1:3)
- ✓ Supply and install Celcon Standard Aerated Concrete Block 3.6N 100mm
- ✓ Supply and install Earthwool DriTherm Cavity Slab Insulation 32 Ultimate 150mm (2.18m<sup>2</sup>)

### Material

Description	Qty	Unit	Rate (£)	Value (£)
Blue Circle Cement 25kg	101.3	each	£5.83	£590.58
Building Sand Bulk Bag	10.4	each	£62.50	£650.00
Sika Maxmix Concentrated Plasticiser 1L	0.8	each	£11.11	£8.44
Celcon Standard Aerated Concrete Block 3.6N 100mm	1778.0	each	£2.23	£3,964.94
London Brick Company Commons	10667.0	each	£1.50	£16,000.50
Staifix Housing Wall Ties HRT4 250mm box of 250	3.0	pack	£41.65	£122.87
Earthwool DriTherm Cavity Slab Insulation 32 Ultimate 150mm (2.18m <sup>2</sup> )	82.6	each	£63.91	£5,277.05

### Labour

Description	Qty	Unit	Rate (£)	Value (£)
Laying concrete blocks	1778.0	each	£1.68	£2,987.04
Laying bricks (half a brick thick)	180.0	m2	£26.40	£4,752.00
Forming cavity	180.0	m2	£0.92	£166.15
Laying wool insulation to cavity wall	180.0	m2	£1.50	£270.00



## Windows

**£5,897.39**

### Windows. Quantity 6:

- ✓ Supply and install 6 x White uPVC Window 1800(W) x 1200(H), Clear glass
- ✓ Includes all ironmongery, double glazing fitting and sealing
- ✓ Fit thermal cavity closers to reveals of openings in external walls to meet building regulation
- ✓ Includes 1 trickle vent
- ✓ Insulated Catnic type or similar cavity lintels bedded in coloured cement sand mortar (1:3)

### Windows (1). Quantity 6:

- ✓ Supply and install 6 x White uPVC Window 750(W) x 1200(H), Clear glass
- ✓ Includes all ironmongery, double glazing fitting and sealing
- ✓ Fit thermal cavity closers to reveals of openings in external walls to meet building regulation
- ✓ Includes 1 trickle vent
- ✓ Insulated Catnic type or similar cavity lintels bedded in coloured cement sand mortar (1:3)

### Material

Description	Qty	Unit	Rate (£)	Value (£)
No Nonsense General Purpose Silicone Clear 310ml	5.9	each	£3.99	£23.70
Masonry Torx Frame Screw 7.5 x 82mm	138.0	each	£0.13	£17.94
Expanding Foam 750ml	4.0	each	£6.91	£27.36
6 x White uPVC Window 1800(W) x 1200(H), Clear glass	6.0	each	£317.18	£1,903.08
Cavity Closer Double Flange 150mm x 2440mm	18.1	each	£12.08	£218.41
Galvanised Clout Nails 2.65 x 30mm 1kg Pack	0.7	kg	£6.66	£4.40
Cavity Wall Lintel CG150/100 2100mm	6.0	each	£132.15	£792.90
UPVC Trickle Vent	12.0	each	£8.90	£106.80
6 x White uPVC Window 750(W) x 1200(H), Clear glass	6.0	each	£207.52	£1,245.12

Cavity Wall Lintel CG150/100 1050mm	6.0	each	£64.00	£384.00
-------------------------------------	-----	------	--------	---------

## Labour

Description	Qty	Unit	Rate (£)	Value (£)
Fit window	6.0	each	£76.00	£456.00
Install Cavity Closers	44.1	m	£3.77	£166.42
Install steel lintel	6.0	each	£10.08	£60.48
Install trickle vents	12.0	each	£5.00	£60.00
Fit window	6.0	each	£67.00	£402.00
Install steel lintel	6.0	each	£4.80	£28.80



## External Doors

**£6,370.70**

### French Door. Quantity: 3 each.

- ✓ Supply and install White uPVC French Door 2.1m - 3 each
- ✓ Fixing in position and sealing, double glazed
- ✓ Complete with ironmongery to include hinges, multi-point locking system and handles
- ✓ Fit insulated cavity closers to meet building regulation
- ✓ Insulated Catnic type or similar cavity lintels bedded in coloured cement sand mortar (1:3)

### Composite Door. Quantity: 3 each.

- ✓ Supply and install Composite Front Door 920 x 2085mm - 3 each
- ✓ Fixing in position and sealing, colour to be agreed
- ✓ Complete with ironmongery to include hinges, multi-point locking system and handles
- ✓ Fit insulated cavity closers to meet building regulation
- ✓ Insulated Catnic type or similar cavity lintels bedded in coloured cement sand mortar (1:3)

## Material

Description	Qty	Unit	Rate (£)	Value (£)
Cavity Closer Double Flange 150mm x 2440mm	12.0	each	£12.08	£144.96
Galvanised Clout Nails 2.65 x 30mm 1kg Pack	0.4	kg	£6.66	£2.53
Cavity Wall Lintel CG150/100 2400mm	3.0	each	£210.46	£631.38
No Nonsense General Purpose Silicone Clear 310ml	4.5	each	£3.99	£17.96
Masonry Torx Frame Screw 7.5 x 82mm	60.0	each	£0.13	£7.80
Expanding Foam 750ml	1.8	each	£6.91	£12.09
White uPVC French Door 2.1m	3.0	each	£833.33	£2,499.99
Composite Front Door 920 x 2085mm	3.0	each	£708.33	£2,124.99
Cavity Wall Lintel CG150/100 1500mm	3.0	each	£91.41	£274.23

## Labour

Description	Qty	Unit	Rate (£)	Value (£)
Install Cavity Closers	25.2	m	£3.77	£95.09
Install steel lintel	3.0	each	£11.52	£34.56
Install french door	3.0	each	£90.91	£272.73
Install front door	3.0	each	£76.92	£230.77
Install steel lintel	3.0	each	£7.20	£21.60



## Roof Trusses

**£15,807.13**

### Roof Roof Pitch 30° Roof area 284.11m²

- ✓ Supply and install 48 roof trusses and bracing;
- A Roof trusses allowance - £184.51 + VAT per each truss;
- ✓ 47 x 95 mm (2" x 4") softwood treated wall plate, bedded on cement sand mortar (1:3)

✓ Fixing with galvanised mild steel wall plate straps at maximum 2.00m centres

## Material

Description	Qty	Unit	Rate (£)	Value (£)
Sawn Timber Treated C16/C24 47 x 95mm x 4.8m	38.4	m	£1.71	£65.66
Brown Plastic Plugs Box of 100	0.6	box	£2.83	£1.70
Heavy Restraint Strap 1200 x 30 x 5mm	22.0	each	£5.71	£125.62
Building Sand Bulk Bag	0.1	each	£62.50	£9.38
Blue Circle Cement 25kg	1.4	each	£5.83	£8.40
Screws 4 x 50mm box of 200	0.5	box	£3.74	£1.87
Sawn Timber Treated C16/C24 47 x 95mm	303.6	m	£1.71	£519.14
Simpson Masonry Joist Hanger 75mm x 165mm	90.0	each	£4.22	£379.80
Heavy Restraint Strap 600 x 28 x 4mm	36.0	each	£2.69	£96.84
63mm Paslode stainless steel angled brads 16ga 2500 Pack	2.0	pack	£41.66	£83.32
Roof Trusses	48.0	each	£184.51	£8,856.48
Screws 5 x 80mm box of 100	672.0	each	£0.05	£31.32

## Labour

Description	Qty	Unit	Rate (£)	Value (£)
Bedding wall plate	37.0	m	£4.40	£162.80
Roof extras labour	74.1	hour	£28.00	£2,074.80
Install trusses	48.0	each	£67.50	£3,240.00

## Plant & Tool

Description	Qty	Term	Unit	Rate (£)	Value (£)
Delivery Cost	1	-	each	£150.00	£150.00



## Pitched Roof Covering

**£16,868.37**

### Plain Range.

- ✓ Supply and install Tyvek Supro Breather Membrane 1 x 50m
- ✓ Fix softwood treated tile batten 25 x 38mm with nails or screws
- ✓ Supply and install Marley Concrete Plain Tiles
- ✓ Fit underlay support tray and roofing felt dressed into gutter
- ✓ Ridge tiles bedded and pointed in coloured mortar
- ✓ Verge tiles pointed in coloured mortar
- ✓ Supalux board undercloak
- ✓ Install Lead flashing and pointing with coloured mortar or grey sealant. Supply:
- ✓ Code 4 Lead Roll 360mm x 6m - 3 rolls

## Material

Description	Qty	Unit	Rate (£)	Value (£)
Tyvek Supro Breather Membrane 1 x 50m	3.9	each	£98.15	£378.86
Plastic Eaves Support tray 1.5m	27.0	each	£2.15	£58.05
Galvanised Clout Nails 2.65 x 30mm 1kg Pack	0.4	kg	£6.66	£2.73
Marley Segmental Ridge Tile Natural Red (Fine Sanded)	40.5	each	£5.76	£233.16
Blue Circle Cement 25kg	7.0	each	£5.83	£40.58
Sharp Sand Bulk Bag	0.7	each	£62.50	£44.38
Undercloak 150 x 1200 mm	15.0	each	£2.40	£36.00
Treated Batten 25 x 38mm	1698.5	m	£0.72	£1,222.92

65mm x 2.65 Galvanized Round Wire Nail 1kg Pack	12.1	pack	£5.00	£60.65
Code 4 Lead Roll 360mm x 6m	3.0	roll	£130.57	£391.71
Marley Concrete Plain Tiles	10182.0	each	£0.51	£5,192.82
Aluminium Clout Nails 38mm 1kg Pack	4.4	pack	£12.15	£53.95
Marley Eaves Tiles	450.0	each	£1.24	£558.00
Marley Tile and Half	90.0	each	£1.18	£106.20

## Labour

Description	Qty	Unit	Rate (£)	Value (£)
Fixing breather membrane	193.2	m2	£1.82	£351.27
Fix eaves support	37.0	m	£3.50	£129.50
Bedding ridge/hips tiles	18.5	m	£25.45	£470.91
Pointing verges, inc fixing clips	18.0	m	£14.74	£265.26
Fix undercloak	18.0	m	£4.00	£72.00
Fixing battens to timber	1698.5	m	£1.50	£2,547.75
Install flashings	13.0	hour	£28.00	£362.88
Fix plain tiles (sloped)	10722.0	each	£0.40	£4,288.80



## Fascia and Soffit

**£2,673.96**

### Upvc. Supply and fit Upvc fascias, bargeboards and soffits:

#### Fascia. Length - 37m

- ✓ Supply and install uPVC White Fascia Board 18 x 225mm x 5m

#### Eave Soffit. Length - 37m

- ✓ Supply and install uPVC White Vented Soffit Board 9 x 200mm x 5m

#### Bargeboard. Length - 18m

- ✓ Supply and install uPVC White Fascia Board 18 x 200mm x 5m

#### Rake Soffit. Length - 18m

- ✓ Supply and install uPVC White Solid Soffit Board 9 x 200mm x 5m

#### Box End. Quantity - 4each

- ✓ Includes forming boxed ends at junction of fascia and barge

### Accessories and Extras:

- ✓ White Soffit Vent - 40 each
- ✓ White External Corner 300mm - 4 each
- ✓ White Fascia Joiner - 15 each
- ✓ White Fascia Board Finial - 2 each

## Material

Description	Qty	Unit	Rate (£)	Value (£)
uPVC White Solid Soffit Board 9 x 200mm x 5m	3.6	each	£21.87	£78.73
White 40mm Plastic Headed Pins x 250	2.2	box	£5.73	£12.61
Nylon Anchor Hammerfix Screws M5x50mm Box of 100	1.1	box	£5.05	£5.56
Treated Batten 19 x 50mm	18.0	m	£1.27	£22.86
uPVC White Fascia Board 18 x 200mm x 5m	3.6	each	£41.77	£150.37
uPVC White Vented Soffit Board 9 x 200mm x 5m	7.4	each	£35.22	£260.63
Treated Batten 25 x 50mm	37.0	m	£0.92	£34.04

uPVC White Fascia Board 18 x 225mm x 5m	7.4	each	£48.69	£360.31
uPVC White Fascia Board 18 x 400mm x 5m	0.4	each	£95.05	£38.02
White External Corner 500mm	4.0	each	£3.90	£15.60
White External Corner 300mm	8.0	each	£1.75	£14.00
White Soffit Vent	40.0	each	£0.43	£17.20
White Fascia Joiner	15.0	each	£4.16	£62.40
White Fascia Board Finial	2.0	each	£4.15	£8.30

## Labour

Description	Qty	Unit	Rate (£)	Value (£)
Install fascia/soffit 150-300mm	110.0	m	£9.22	£1,013.82
Fixing battens to masonry	55.0	m	£3.38	£185.63
Install box end	4.0	each	£22.22	£88.89
Labour for accessories and extras	15.3	hour	£20.00	£305.00



## Rainwater Goods

**£713.72**

### Rainwater Goods.

#### uPVC Gutters

Half Round Gutter 3 m length - Black - 12  
Half Round Union Bracket - Black - 12  
Half Round External Stop End - Black - 4  
Half Round Fascia Bracket - Black - 48  
Half Round Running Outlet - Black - 4

#### uPVC Downpipes

Round Downpipe 2.5 m lengths 68mm - Black - 8  
Half Round Clip 68 mm - Black - 16  
Round Socket 68 mm Black - 4  
Round Bend 92.5° Black 68 mm - 8  
Round Bend 112.5° Black 68 mm - 8

## Material

Description	Qty	Unit	Rate (£)	Value (£)
Round Downpipe 2.5 m lengths 68mm - Black	8.0	each	£7.73	£61.84
Half Round Clip 68 mm - Black	16.0	each	£0.73	£11.68
Round Socket 68 mm Black	4.0	each	£1.47	£5.88
Round Bend 92.5° Black 68 mm	8.0	each	£2.59	£20.72
Round Bend 112.5° Black 68 mm	8.0	each	£2.59	£20.72
Half Round Gutter 3 m length - Black	12.0	each	£5.44	£65.28
Half Round External Stop End - Black	4.0	each	£1.47	£5.88
Half Round Fascia Bracket - Black	48.0	each	£0.65	£31.20
Half Round Union Bracket - Black	12.0	each	£2.22	£26.64
Half Round Running Outlet - Black	4.0	each	£2.97	£11.88

## Labour

Description	Qty	Unit	Rate (£)	Value (£)
Install rainwater goods and accessories	22.6	hour	£20.00	£452.00

Subtotal:	£126,432.63
VAT @ 20%:	£25,286.53
<b>Total :</b>	<b>£151,719.16</b>

---